BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35737

APPROVED SCHEDULE - B

EE/BTF[illegible]3MP/E-PMT/03/2019-20, Date: 14.05.2019

Improvements to Basketball Ground in Sahakaranagara in ward no.07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH J N (SRI CHOWDESHWARI CONSTRUCTIONS)	
				In Figures	In Words
1	111.4	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)	Cum	110.0	Rupees One Hundred Ten Only
2	30	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.13, It.4.3)	Cum	4700.0	Rupees Four Thousand Seven Hundred Only
3	178	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.Pg No. 27, Item No.5.29.1	Nos	430.0	Rupees Four Hundred Thirty Only
4	80.1	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. Page No. 124 / Item No. 15.80	Sqm	35.0	Rupees Thirty Five Only
5	200	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (P.No. 103, I.No. 14.6)	Sqm	900.0	Rupees Nine Hundred Only
6	18	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.9	Cum	5300.0	Rupees Five Thousand Three Hundred Only
7	40	KSRB 15.1.3 Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 115/ Item No. 15.3	Sqm	125.0	Rupees One Hundred Twenty Five Only
8	2.25	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6	Cum	5400.0	Rupees Five Thousand Four Hundred Only

Sharath

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH J N (SRI CHOWDESHWARI CONSTRUCTIONS)	
				In Figures	In Words
9	42	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) Page No. 262 / Item No. 37.2	Mtr	800.0	Rupees Eight Hundred Only
10	120	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. Page No. 262 / Item No. 37.4	Mtr	380.0	Rupees Three Hundred Eighty Only
11	105	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint Page No. 262 / Item No. 37.3	Sqm	680.0	Rupees Six Hundred Eighty Only
12	357	KSRB-15-18.1:Applying additional one coat (excluding priming coat) on previoulsy painted wood surface and /or wood based surface with enamle paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, inlcuding cost of materials, labour, complete a sper specificationss. Pg No.123, Item No.18-18.1	Sqm	40.0	Rupees Forty Only
13	3	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300 Page No. 255, Item No. 34.7.8, PWD SR 2018-19	Mtr	5300.0	Rupees Five Thousand Three Hundred Only
14	0.34	Providing 100mm and down size nominal size. (Pg No.I.Item No.23)	Cum	900.0	Rupees Nine Hundred Only
15	0.23	Providing 40mm and down size nominal size (Pg No.II.Item No.25)	Cum	920.0	Rupees Nine Hundred Twenty Only
16	0.23	Providing 20mm and down size nominal size (Pg No.II.Item No.28)	Cum	920.0	Rupees Nine Hundred Twenty Only
17	0.17	Providing Fine aggrgate 2.36mm nominal size (Pg No.II.Item No.32)	Cum	900.0	Rupees Nine Hundred Only
18	111.4	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 136, item No. 17.1)	Cum	90.0	Rupees Ninety Only

Sharath

Signature of the Contractor

5/08

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/08